

数量総括表

(補助)

名 称	種 別	細 別	単 位	数	量	設 計 数 量	備 考
舗装版切断工	As t=15cm以下		m		15.10	15	
舗装版切断工	Co t=15cm以下		m		29.00	29	
舗装版直接掘削積込工	As		m ²		19.80	20	
舗装版直接掘削積込工	Co		m ²		25.73	26	
舗装版直接掘削積込工	As		m ²		56.70	57	
舗装版直接掘削積込工	Co		m ²		197.43	197	
舗装版直接掘削積込工	As		m ²		4,289.44	4,290	
残塊処分工 As塊			m ³		0.59	1	
残塊処分工 As塊			m ³		1.70	2	
残塊処分工 As塊			m ³		191.49	191	
残塊処分工 Co塊			m ³		2.57	3	
残塊処分工 Co塊			m ³		19.74	20	
建設廃棄物処分費	As塊		m ³		193.78	194	
建設廃棄物処分費	Co塊		m ³		22.31	22	
汚泥処分工			m ³		0.09	0.1	
不陸整正工		補足材無し	m ²		76.50	77	
不陸整正工		補足材無し	m ²		1,149.09	1,150	
不陸整正工	RC-40	補足材1cm	m ²		223.16	223	
不陸整正工	RC-40	補足材2cm	m ²		3,140.35	3,140	
コンクリート舗装工	18-8-25BB	t=10cm	m ²		299.66	300	
型枠工			m ²		2.20	2	
表層工	再生密粒度As(13)	t=4cm	m ²		4,289.44	4,290	
機械掘削工			m ³		5.36	10	
区画線工	白色 実線	t=15cm	m		24.00	24	
区画線工	白色 ゼブラ	t=30cm	m		6.30	6	
区画線工	白色 矢印・記号・文字	t=15cm換算	m		85.40	85	

数量総括表						
(単独)						
名 称	種 別	細 別	単 位	数 量	設 計 数 量	備 考
舗装切断工	Con t=15cm以下		m	3.75	4	
舗装版直接掘削積込工	As		m ²	25.20	25	
舗装版直接掘削積込工	Co		m ²	33.06	33	
舗装版直接掘削積込工	As		m ²	271.17	271	
舗装版直接掘削積込工	Co		m ²	66.54	67	
舗装版直接掘削積込工	As		m ²	204.27	204	
残塊処分工 As塊			m ³	0.76	1	
残塊処分工 As塊			m ³	11.25	11	
残塊処分工 As塊			m ³	8.65	9	
残塊処分工 Co塊			m ³	3.31	3	
残塊処分工 Co塊			m ³	6.65	7	
建設廃棄物処分費	As塊		m ³	20.66	21	
建設廃棄物処分費	Co塊		m ³	9.96	10	
汚泥処分工			m ³	0.01	0.01	
不陸整正工		補足材無し	m ²	25.20	25	
不陸整正工		補足材無し	m ²	151.84	152	
不陸整正工	RC-40	補足材1cm	m ²	33.06	33	
不陸整正工	RC-40	補足材2cm	m ²	348.13	348	
コンクリート舗装工	18-8-25BB	t=10cm	m ²	58.26	58	
型枠工			m ²	3.65	4	
表層工	再生密粒度As(13)	t=4cm	m ²	541.98	542	
機械掘削工			m ³	1.76	2	
区画線工	白色 ゼブラ	t=30cm	m	5.00	5	
区画線工	白色 矢印・記号・文字	t=15cm換算	m	23.60	24	

数 量 計 算 書

(補助)

名 称	種 別	計 算 式	単 位	数 量
舗装版切断工	アスファルト t=15cm以下		m	15.10
舗装版切断工	コンクリート t=15cm以下		m	29.00
舗装版 直接掘削積込工	As・Con	コンクリート 25.73 アスファルト 19.80 + 0.00	m ²	45.53
舗装版 直接掘削積込工	As・Con	コンクリート 197.43 アスファルト 56.70 + 0.00	m ²	254.13
舗装版 直接掘削積込工	As・Con	アスファルト 1,149.09 + 3,140.35	m ²	4,289.44
残塊処分工 As塊		19.80 × 0.03 + 0.00 × 0.04		
		合計=	m ³	0.59
残塊処分工 As塊		56.70 × 0.03 + 0.00 × 0.04		
		合計=	m ³	1.70
残塊処分工 As塊		1,149.09 × 0.03 + 0.00 × 0.04 3,140.35 × 0.05		
		合計=	m ³	191.49
残塊処分工 Con塊			m ³	—
残塊処分工 Con塊		25.73 × 0.10	m ³	2.57
残塊処分工 Con塊		197.43 × 0.10	m ³	19.74
残塊処分工 Con塊			m ³	—
建設廃材処理費	As塊		m ³	193.78
建設廃材処理費	Con塊		m ³	22.31
路盤工 (t=7cm)			m ²	—
不陸整正工	Co舗装部		m ²	—
不陸整正工			m ²	76.50

数量計算書

(補助)

名 称	種 別	計 算 式	単 位	数 量
不陸整正工			m ²	1,149.09
不陸整正工 (補足材 1cm)		既設舗装版厚 t=4cm t=5cm t=6cm t=7cm t=8cm t=9cm t=10cm $223.16 \times 0.01 = 2.23$ 合計V= 合計A= 補足材平均厚V/A=	m ²	223.16
不陸整正工 (補足材 2cm)		既設舗装版厚 t=4cm t=5cm t=6cm t=7cm t=8cm t=9cm t=10cm $3,140.35 \times 0.02 = 62.81$ $62.81 - 5.36 = 57.45$ 合計V= 合計A= 補足材平均厚V/A=	m ²	3,140.35
表層工 (t=4cm)	再生密粒度As(13)		m ²	—
コンクリート舗装工 (t=10cm)	コンクリート舗装		m ²	299.66
型枠工		6工区 No.3+3.0~No.4+5.0 $L(17+4+1) \times 0.1 = 22 \times 0.1$	m ²	2.20
表層工 (t=4cm)	再生密粒度As(13)		m ²	4,289.44
機械掘削工		平均掘削 $0.90 \times 0.07 \times 85$ 合計V=	m ³	5.36
補足材流用			m ³	5.36

数量計算書

（補助）

名 称	規 格	計 算 式	数 量
-----	-----	-------	-----

白色・実線	t=15cm	L =	2工区 12.0	+	2工区 12.0	
-------	--------	-----	-------------	---	-------------	--

--	--	--	--

		=	m 6.3
--	--	---	----------

白色		1工区	2工区	2工区	3工区		m			
文字・記号	t=15cm換算	L = 11.8	+	11.8	+	43.2	+	18.6	=	85.4

5

数 量 計 算 書

(単独)

名 称	種 別	計 算 式	単 位	数 量
舗装版切断工	アスファルト t=15cm以下		m	—
舗装版切断工	コンクリート t=15cm以下		m	3.75
舗装版 直接掘削積込工	As・Con	コンクリート 33.06 アスファルト 25.20 + 0.00	m ²	58.26
舗装版 直接掘削積込工	As・Con	コンクリート 66.54 アスファルト 115.65 + 155.52	m ²	337.71
舗装版 直接掘削積込工	As・Con	アスファルト 78.20 + 126.07	m ²	204.27
残塊処分工 As塊		25.20 × 0.03 + 0.00 × 0.04		
		合計=	m ³	0.76
残塊処分工 As塊		115.65 × 0.03 + 0.00 × 0.04 155.52 × 0.05		
		合計=	m ³	11.25
残塊処分工 As塊		78.20 × 0.03 + 0.00 × 0.04 126.07 × 0.05		
		合計=	m ³	8.65
残塊処分工 Con塊			m ³	—
残塊処分工 Con塊		33.06 × 0.10	m ³	3.31
残塊処分工 Con塊		66.54 × 0.10	m ³	6.65
残塊処分工 Con塊			m ³	—
建設廃材処理費	As塊		m ³	20.66
建設廃材処理費	Con塊		m ³	9.96
不陸整正工	Co舗装部		m ²	—
不陸整正工			m ²	25.20
不陸整正工			m ²	151.84

数 量 計 算 書

(単独)

名 称	種 別	計 算 式	単 位	数 量
不陸整正工 (補足材 1cm)		既設舗装版厚 t=4cm t=5cm t=6cm t=7cm t=8cm t=9cm t=10cm $33.06 \times 0.01 = 0.33$ 合計V= 0.33 合計A= 33.06 補足材平均厚V/A= 0.01	m ²	33.06
不陸整正工 (補足材 2cm)		既設舗装版厚 t=4cm $281.59 \times 0.02 = 5.63$ t=5cm t=6cm t=7cm t=8cm t=9cm t=10cm $66.54 \times 0.07 = 4.66$ 合計V= 10.29-1.76=8.53 合計A= 348.13 補足材平均厚V/A= 0.02	m ²	348.13
表層工 (t=4cm)	再生密粒度As(13)		m ²	—
コンクリート舗装工 (t=10cm)	コンクリート舗装		m ²	58.26
型枠工		6工区 No.4+5.0~No.5+10.0 $L(10.5+2+1+1.5+7+3) \times 0.1 + (1.5+7+3) \times 0.1 = 36.5 \times 0.1$	m ²	3.65
表層工 (t=4cm)	再生密粒度As(13)		m ²	541.98
機械掘削工		平均掘削 $0.90 \times 0.07 \times 28$ 合計V= 1.764	m ³	1.76
補足材流用			m ³	1.76

数量計算書

(単独)

名 称	規 格	計 算 式	数 量
-----	-----	-------	-----

白色・ゼブラ	t=30cm	L =	4工区 2.5	+	4工区 2.5	
--------	--------	-----	------------	---	------------	--

		=	m 5.0
--	--	---	----------

--	--	--	--

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		幅 員	面 積	幅 員	面 積	幅 員	面 積		
																	【幅員は 5cm 単位とする】
1	No. 0	3.00	1.70		6.50		8.20										As舗装 t = 5cm
	No. 0 + 3.00		1.70	5.10	2.95	14.18	4.65	19.28									
1	No. 0 + 3.00	9.00	1.70		2.95		4.65										As舗装 t = 5cm
	No. 0 + 12.00		1.70	15.30	2.80	25.88	4.50	41.18									
1	No. 0 + 12.00	1.50	1.70		2.30		4.00										As舗装 t = 5cm
	No. 0 + 13.50		1.70	2.55	2.30	3.45	4.00	6.00									
1	No. 0 + 13.50	1.50	1.70		2.65		4.35										As舗装 t = 5cm
	No. 0 + 15.00		1.70	2.55	3.00	4.24	4.70	6.79	1.50								
1	No. 0 + 15.00	5.00	1.70		3.00		4.70										As舗装 t = 5cm
	No. 1		1.70	8.50	3.15	15.38	4.85	23.88	5.00								
1	No. 1	3.20	1.70		3.15		4.85										As舗装 t = 5cm
	No. 1 + 3.20		1.70	5.44	3.30	10.32	5.00	15.76	3.20								
1	No. 1 + 3.20	7.30	1.70		3.00		4.70										As舗装 t = 5cm
	No. 1 + 10.50		1.70	12.41	3.25	22.81	4.95	35.22									
1	No. 1 + 10.50	9.50	1.70		3.50		5.20										As舗装 t = 5cm
	No. 2		1.70	16.15	3.40	32.78	5.10	48.93									
1	No. 2	20.00	1.70		3.40		5.10										As舗装 t = 5cm
	No. 3		1.70	34.00	3.30	67.00	5.00	101.00									
1	No. 3	12.00	1.70		3.30		5.00										As舗装 t = 5cm
	No. 3 + 12.00		1.70	20.40	3.50	40.80	5.20	61.20									
1	No. 3 + 12.00	4.00	1.70		3.50		5.20										As舗装 t = 5cm
	No. 3 + 16.00		1.70	6.80	2.50	12.00	4.20	18.80									
1	No. 3 + 16.00	4.00	1.70		2.50		4.20										As舗装 t = 5cm
	No. 4		1.70	6.80	2.50	10.00	4.20	16.80									
1	No. 4	20.00	1.70		2.50		4.20										As舗装 t = 5cm
	No. 5		1.70	34.00	2.70	52.00	4.40	86.00									
1	No. 5	20.00	1.70		2.70		4.40										As舗装 t = 5cm
	No. 6		1.70	34.00	2.95	56.50	4.65	90.50									
1	No. 6	20.00	1.70		2.95		4.65										As舗装 t = 5cm
	No. 7		1.70	34.00	2.90	58.50	4.60	92.50									
1	No. 7	20.00	1.70		2.90		4.60										As舗装 t = 5cm
	No. 8		1.70	34.00	2.90	58.00	4.60	92.00									
1	No. 8	20.00	1.70		2.90		4.60										As舗装 t = 5cm
	No. 9		1.70	34.00	2.95	58.50	4.65	92.50									
1	No. 9	20.00	1.70		2.95		4.65										As舗装 t = 5cm
	No. 10		1.70	34.00	2.80	57.50	4.50	91.50									

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		幅 員	面 積	幅 員	面 積	幅 員	面 積		
1	No. 10	20.00	1.70		2.80		4.50										As舗装 t = 5cm
	No. 11		1.70	34.00	2.85	56.50	4.55	90.50									
1	No. 11	20.00	1.70		2.85		4.55										As舗装 t = 5cm
	No. 12		1.70	34.00	2.95	58.00	4.65	92.00									
1	No. 12	18.80	1.70		2.95		4.65										As舗装 t = 5cm
	No. 12 + 18.80		1.70	31.96	2.80	54.05	4.50	86.01									
1	No. 12 + 18.80	1.20	1.70		2.80		4.50										As舗装 t = 5cm
	No. 13		1.70	2.04	2.85	3.39	4.55	5.43									
1	No. 13	1.50	1.70		2.85		4.55										As舗装 t = 5cm
	No. 13 + 1.50		1.70	2.55	3.05	4.43	4.75	6.98									
1	No. 13 + 1.50	1.50	1.70		3.05		4.75										As舗装 t = 5cm
	No. 13 + 3.00		1.70	2.55	4.85	5.93	6.55	8.48									
1	No. 13 + 3.00	1.00	1.70		5.40		7.10										As舗装 t = 5cm
	No. 13 + 4.00		1.70	1.70	5.45	5.43	7.15	7.13									
1	No. 13 + 4.00	4.00	1.70		6.20		7.90										As舗装 t = 5cm
	No. 13 + 8.00		1.70	6.80	6.40	25.20	8.10	32.00									
1	No. 13 + 8.00	1.50	1.70		6.40		8.10										As舗装 t = 5cm
	No. 13 + 9.50		1.70	2.55	3.00	7.05	4.70	9.60									
1	No. 13 + 9.50	1.50	1.70		3.00		4.70										As舗装 t = 5cm
	No. 13 + 11.00		1.70	2.55	2.70	4.28	4.40	6.83									
1	No. 13 + 11.00	9.00	1.70		2.70		4.40										As舗装 t = 5cm
	No. 14		1.70	15.30	2.65	24.08	4.35	39.38									
1	No. 14	20.00	1.70		2.65		4.35										As舗装 t = 5cm
	No. 15		1.70	34.00	2.85	55.00	4.55	89.00									
1	No. 15	20.00	1.70		2.85		4.55										As舗装 t = 5cm
	No. 16		1.70	34.00	2.80	56.50	4.50	90.50									
1	No. 16	20.00	1.70		2.80		4.50										As舗装 t = 5cm
	No. 17		1.70	34.00	2.65	54.50	4.35	88.50									
1	No. 17	20.00	1.70		2.65		4.35										As舗装 t = 5cm
	No. 18		1.70	34.00	2.70	53.50	4.40	87.50									
1	No. 18	20.00	1.70		2.70		4.40										As舗装 t = 5cm
	No. 19		1.70	34.00	2.65	53.50	4.35	87.50									
1	No. 19	10.00	1.70		2.65		4.35										As舗装 t = 5cm
	No. 19 10.00		1.70	17.00	2.65	26.50	4.35	43.50									
1	No. 19 10.00	10.00								1.70				4.35			As舗装 t = 5cm
	No. 20									1.70	17.00		26.25	4.30	43.25		
1	No. 20	20.00								1.70		2.60		4.30			As舗装 t = 5cm
	No. 21									1.70	34.00	2.60	52.00	4.30	86.00		

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		幅 員	面 積	幅 員	面 積	幅 員	面 積		
1	No. 21 No. 21 + 14.50	14.50								1.70 1.70	24.65	2.60 2.95	40.24	4.30 4.65	64.89	As舗装 t = 5cm	
1	No. 21 14.50 No. 21 16.00	1.50								1.70 1.70	2.55	3.50 6.60	7.58	5.20 8.30	10.13	As舗装 t = 5cm	
	No. No.																
2	No. 0 + 3.20 No. 0 + 5.70	2.50	1.05 1.05	2.63	12.65 12.15	31.00	13.70 13.20	33.63								As舗装 t = 5cm	
2	No. 0 + 5.70 No. 0 + 9.70	4.00	1.05 1.05	4.20	9.10 6.45	31.10	10.15 7.50	35.30								As舗装 t = 5cm	
2	No. 0 + 9.70 No. 0 + 13.00	3.30	1.05 1.05	3.47	6.15 5.50	19.22	7.20 6.55	22.69								As舗装 t = 5cm	
2	No. 0 + 13.00 No. 0 + 16.00	3.00	1.05 1.05	3.15	3.55 2.85	9.60	4.60 3.90	12.75								As舗装 t = 5cm	
2	No. 0 + 16.00 No. 1	4.00	1.05 1.05	4.20	2.25 2.35	9.20	3.30 3.40	13.40								As舗装 t = 5cm	
2	No. 1 No. 2	20.00	1.05 1.05	21.00	2.35 2.50	48.50	3.40 3.55	69.50								As舗装 t = 5cm	
2	No. 2 No. 2 + 17.00	17.00	1.05 1.05	17.85	2.50 2.75	44.63	3.55 3.80	62.48								As舗装 t = 5cm	
2	No. 2 + 17.00 No. 2 + 18.50	1.50	1.05 1.05	1.58	2.75 3.20	4.46	3.80 4.25	6.04								As舗装 t = 5cm	
2	No. 2 + 18.50 No. 2 + 19.60	1.10	1.05 1.05	1.16	3.20 4.25	4.09	4.25 5.30	5.25								As舗装 t = 5cm	
2	No. 2 + 19.60 No. 3	0.40														As舗装 t = 5cm	
2	No. 3 No. 3 + 4.00	4.00	1.05 1.05	4.20	4.05 3.85	15.80	5.10 4.90	20.00								As舗装 t = 5cm	
2	No. 3 + 4.00 No. 3 + 8.00	4.00	1.05 1.05	4.20	3.85 3.95	15.60	4.90 5.00	19.80								As舗装 t = 5cm	
2	No. 3 + 8.00 No. 3 + 19.00	11.00	1.05 1.05	11.55	5.00 3.95	43.45	5.00 5.00	55.00								As舗装 t = 5cm	
2	No. 3 + 19.00 No. 4	1.00	1.05 1.05	1.05	3.95 4.30	4.13	5.00 5.35	5.18								As舗装 t = 5cm	
2	No. 4 No. 5	20.00	1.05 1.05	21.00	4.30 4.40	87.00	5.35 5.45	108.00								As舗装 t = 5cm	
2	No. 5 No. 6	20.00	1.05 1.05	21.00	4.40 4.45	88.50	5.45 5.50	109.50								As舗装 t = 5cm	

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		延長	幅 員	面 積	幅 員	面 積	幅 員		
2	No. 6	20.00	1.05		4.45		5.50										As舗装 t = 5cm
	No. 7		1.05	21.00	4.35	88.00	5.40	109.00									
2	No. 7	20.00	1.05		4.35		5.40										As舗装 t = 5cm
	No. 8		1.05	21.00	4.45	88.00	5.50	109.00									
2	No. 8	20.00	1.05		4.45		5.50										As舗装 t = 5cm
	No. 9		1.05	21.00	4.40	88.50	5.45	109.50									
2	No. 9	20.00	1.05		4.40		5.45										As舗装 t = 5cm
	No. 10		1.05	21.00	4.45	88.50	5.50	109.50									
2	No. 10	12.00	1.05		4.45		5.50										As舗装 t = 5cm
	No. 10 + 12.00		1.05	12.60	4.35	52.80	5.40	65.40									
2	No. 10 + 12.00	8.00	1.05		5.35		6.40										As舗装 t = 5cm
	No. 11		1.05	8.40	5.35	42.80	6.40	51.20									
2	No. 11	0.50	1.05		5.35		6.40										As舗装 t = 5cm
	No. 11 + 0.50		1.05	0.53	4.95	2.57	6.00	3.10									
2	No. 11 + 0.50	19.50	1.05		4.55		5.60										As舗装 t = 5cm
	No. 12		1.05	20.48	4.65	89.70	5.70	110.18									
2	No. 12	20.00	1.05		4.65		5.70										As舗装 t = 5cm
	No. 13		1.05	21.00	4.50	91.50	5.55	112.50									
2	No. 13	20.00	1.05		4.50		5.55										As舗装 t = 5cm
	No. 14		1.05	21.00	4.40	89.00	5.45	110.00									
2	No. 14	7.00	1.05		4.40		5.45										As舗装 t = 5cm
	No. 14 + 7.00		1.05	7.35	4.35	30.63	5.40	37.98	5.40								
2	No. 14 7.00	2.00	1.05		4.35		5.40										As舗装 t = 5cm
	No. 14 9.00		1.05	2.10	5.35	9.70	6.40	11.80									
2	No. 14 9.00	5.00	1.05		5.35		6.40										As舗装 t = 5cm
	No. 14 14.00		1.05	5.25	5.35	26.75	6.40	32.00									
2	No. 14 14.00	2.00	1.05		5.35		6.40										As舗装 t = 5cm
	No. 14 16.00		1.05	2.10	4.35	9.70	5.40	11.80									
3	No. No.	20.00															As舗装 t = 5cm
	No. 0		1.05		4.30		5.35										
3	No. 1	20.00	1.05	21.00	4.30	86.00	5.35	107.00									As舗装 t = 5cm
	No. 2		1.05	21.00	4.35	86.50	5.40	107.50									
3	No. 2	20.00	1.05		4.35		5.40										As舗装 t = 5cm
	No. 3		1.05	21.00	4.40	87.50	5.45	108.50									
3	No. 3	20.00	1.05		4.40		5.45										As舗装 t = 5cm
	No. 4		1.05	21.00	4.55	89.50	5.60	110.50									

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		延長	幅 員	面 積	幅 員	面 積	幅 員		
3	No. 4	20.00	1.05		4.55		5.60										As舗装 t =5cm
	No. 5		1.05	21.00	4.30	88.50	5.35	109.50									
3	No. 5	20.00	1.05		4.30		5.35										As舗装 t =5cm
	No. 6		1.05	21.00	4.30	86.00	5.35	107.00									
3	No. 6	20.00	1.05		4.30		5.35										As舗装 t =5cm
	No. 7		1.05	21.00	4.35	86.50	5.40	107.50									
3	No. 7	14.50	1.05		4.35		5.40										As舗装 t =5cm
	No. 7 + 14.50		1.05	15.23	4.40	63.43	5.45	78.66									
3	No. 7 + 14.50	5.50	1.05		5.20		6.25										As舗装 t =5cm
	No. 8		1.05	5.78	4.05	25.43	5.10	31.21									
3	No. 8	4.50	1.05		4.05		5.10										As舗装 t =5cm
	No. 8 + 4.50		1.05	4.73	4.10	18.33	5.15	23.06									
3	No. 8 + 4.50	6.00	1.05		4.10		5.15										As舗装 t =5cm
	No. 8 + 10.50		1.05	6.30	2.75	20.55	3.80	26.85									
	No. No.																
4	No. 0	3.50								1.05		3.75		4.80			As舗装 t =5cm
	No. 0 + 3.50									1.05	3.68	3.85	13.30	4.90	16.98		
4	No. + 3.50	16.50								1.05		2.95		4.00			As舗装 t =5cm
	No. 1								1.05	17.33	2.85	47.85	3.90	65.18			
4	No. 1	20.00								1.05		2.85		3.90			As舗装 t =5cm
	No. 2								1.05	21.00	2.80	56.50	3.85	77.50			
	No. No.																
5	No. 0	1.00								1.55		2.70		4.25			As舗装 t =5cm
	No. 0 + 1.00									1.55	1.55	1.70	2.20	3.25	3.75		
5	No. 0 + 1.00	2.70								1.55		1.70		3.25			As舗装 t =5cm
	No. 0 + 3.70									1.55	4.19	1.75	4.65	3.30	8.84		
5	No. 0 + 3.70	7.10								1.55		1.75		3.30			As舗装 t =5cm
	No. 0 + 10.80									1.55	11.01	1.75	12.42	3.30	23.43		
5	No. 0 + 10.80	8.00								1.55		2.35		3.90			As舗装 t =5cm
	No. 0 + 18.80									1.55	12.40	2.30	18.60	3.85	31.00		
5	No. 0 + 18.80	1.20								1.55		2.30		3.85			Con舗装 t =10cm
	No. 1									1.55	1.86	2.35	2.79	3.90	4.65		
5	No. 1	20.00								1.55		2.35		3.90			Con舗装 t =10cm
	No. 2									1.55	31.00	2.30	46.50	3.85	77.50		
5	No. 2	5.80								1.55		2.30		3.85			Con舗装 t =10cm
	No. 2 + 5.80									1.55	8.99	2.30	13.34	3.85	22.33		

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断	取壊し工・不陸整正工				本復旧工		舗装切断	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		延長	幅 員	面 積	幅 員	面 積	幅 員		
5	No. 2 + 5.80	1.70								1.55		2.30		3.85		Con舗装 t =10cm	
	No. 2 + 7.50									1.55	2.64	2.30	3.91	3.85	6.55		
	No. No.																

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			仮舗装分(t=3cm)		影響復旧分		表層工(t=4cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		幅 員	面 積	幅 員	面 積	幅 員	面 積		
	合 計	舗装切断							15.10								既設舗装版 上段(Con舗装) 下段(As舗装)
		FALSE									115.65		66.54 155.52				
				1,149.09		3,140.35					78.20		126.07				
	施工延長 L= 986.80m																
	補助 L= 852.90m																
	単独 L= 133.90m			1,149.09		3,140.35		4,289.44			193.85		348.13		541.98		

既設		舗装版取壊し 内訳表							上段(Con舗装) 下段(As舗装)		不陸整正 内訳表						
(補助)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	(補助)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm
												3,140.35					
			3,140.35														
(単独)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	(単独)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm
								66.54									
			155.52									281.59					66.54
			126.07														

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		延長	幅 員	面 積	幅 員	面 積	幅 員		
																	【幅員は 5cm 単位とする】
6	No. 0		0.90		8.90		9.80										
	No. 0 + 2.00	2.00	0.90	1.80	6.70	15.60	7.60	17.40									Con舗装 t =10cm
6	No. 0 + 2.00		0.90		6.70		7.60										
	No. 0 + 4.00	2.00	0.90	1.80	5.50	12.20	6.40	14.00									Con舗装 t =10cm
6	No. 0 + 4.00		0.90		5.50		6.40										
	No. 0 + 6.00	2.00	0.90	1.80	4.10	9.60	5.00	11.40									Con舗装 t =10cm
6	No. 0 + 6.00		0.90		4.10		5.00										
	No. 0 + 9.50	3.50	0.90	3.15	2.25	11.11	3.15	14.26									Con舗装 t =10cm
6	No. 0 + 9.50		0.90		2.25		3.15										
	No. 0 + 19.10	9.60	0.90	8.64	2.95	24.96	3.85	33.60	10.00								Con舗装 t =10cm
6	No. 0 + 19.10		0.90		2.95		3.85										
	No. 1 +	0.90	0.90	0.81	2.95	2.65	3.85	3.46									Con舗装 t =10cm
6	No. 1		0.90		2.95		3.85										
	No. 1 + 18.50	18.50	0.90	16.65	2.90	54.11	3.80	70.76									Con舗装 t =10cm
6	No. 1 + 18.50		0.90		2.90		3.80										
	No. 2	1.50	0.90	1.35	3.10	4.50	4.00	5.85									Con舗装 t =10cm
6	No. 2		0.90		3.10		4.00										
	No. 2 + 0.30	0.30	0.90	0.27	3.20	0.95	4.10	1.22									Con舗装 t =10cm
6	No. 2 + 0.30		0.90		2.55		3.45										
	No. 2 + 1.00	0.70	0.90	0.63	2.55	1.79	3.45	2.42									Con舗装 t =10cm
6	No. 2 + 1.00		0.90		2.75		3.65										
	No. 3	19.00	0.90	17.10	2.70	51.78	3.60	68.88	19.00								Con舗装 t =10cm
6	No. 3		0.90		2.70		3.60										
	No. 3 + 3.00	3.00	0.90	2.70	2.75	8.18	3.65	10.88									Con舗装 t =10cm
6	No. 3 + 3.00		0.90		1.60		2.50										
	No. 4	17.00	0.90	15.30	0.95	21.68	1.85	36.98									Con舗装 t =10cm
6	No. 4		0.90		0.95		1.85										
	No. 4 + 4.00	4.00	0.90	3.60	0.70	3.30	1.60	6.90									Con舗装 t =10cm
6	No. 4 + 4.00		0.90		0.70		1.60										
	No. 4 + 5.00	1.00	0.90	0.90	0.80	0.75	1.70	1.65									Con舗装 t =10cm
6	No. 4 + 5.00									0.90		0.80		1.70			
	No. 4 + 15.50	10.50								0.90	9.45	0.95	9.19	1.85	18.64		Con舗装 t =10cm
6	No. 4 + 15.50									0.90		0.95		1.85			
	No. 4 + 17.50	2.00								0.90	1.80	1.45	2.40	2.35	4.20		Con舗装 t =10cm
6	No. 4 + 17.50									0.90		1.45		2.35			
	No. 4 + 18.50	1.00								0.90	0.90	1.15	1.30	2.05	2.20		Con舗装 t =10cm

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断 延長	取壊し工・不陸整正工				本復旧工		舗装切断 延長	
			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		幅 員	面 積	幅 員	面 積	幅 員	面 積		
6	No. 4 + 18.50	1.50								0.90		1.15		2.05			Con舗装 t =10cm
	No. 5									0.90	1.35	1.00	1.61	1.90	2.96		
6	No. 5 + 7.00	7.00								0.90		1.00		1.90			Con舗装 t =10cm
	No. 5 + 7.00									0.90	6.30	1.25	7.88	2.15	14.18		
6	No. 5 + 10.00	3.00								0.90		1.25		2.15			Con舗装 t =10cm
	No. 5 + 10.00									0.90	2.70	1.55	4.20	2.45	6.90		
6	No. 5 + 11.00	1.00								0.90		1.55		2.45			Con舗装 t =10cm
	No. 5 + 11.00									0.90	0.90	1.90	1.73	2.80	2.63		
6	No. 5 + 13.00	2.00								0.90		1.90		2.80			Con舗装 t =10cm
	No. 5 + 13.00									0.90	1.80	2.85	4.75	3.75	6.55	3.75	
	No. No.																

舗 装 面 積 計 算 書

工区	測 点	距 離	下水(補助)							下水(単独)							摘 要
			取壊し工・不陸整正工				本復旧工		舗装切断	取壊し工・不陸整正工				本復旧工		舗装切断	
			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			仮舗装分(t=3cm)		影響復旧分		コンクリート舗装工(t=10cm)			
			幅 員	面 積	幅 員	面 積	幅 員	面 積		延長	幅 員	面 積	幅 員	面 積	幅 員		
	合 計	舗装切断							29.00							3.75	既設舗装版 上段(Con舗装) 下段(As舗装)
						25.73						33.06					
				19.80							25.20						
		FALSE		56.70		197.43											
	施工延長 L= 113.00m																
	補助 L= 85.00m			76.50		223.16		299.66			25.20		33.06		58.26		
	単独 L= 28.00m																

既設		舗装版取壊し 内訳表							上段(Con舗装) 下段(As舗装)		不陸整正 内訳表							
(補助)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	(補助)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	
								25.73									223.16	
								197.43										
(単独)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	(単独)		t =4cm	t =5cm	t =6cm	t =7cm	t =8cm	t =9cm	t =10cm	
								33.06									33.06	

各種計算法書

カッター汚泥量算出表(補助)

・発生汚泥量

			施工延長(m)		舗装切断深さ(m)		合計
アスファルト,Co舗装版厚			×		×	=	
15<t≤30cm	0.023	×	0.00 m	×		= 0.00 m3	
t≤15cm	0.023	×	15.1 m	×	0.05	= 0.02 m3	
t≤15cm	0.023	×	29.0 m	×	0.10	= 0.07 m3	
	0.023	×	m	×		= 0.00 m3	

0.09 m3

各種計算書

カッター汚泥量算出表(単独)

・発生汚泥量

				施工延長(m)		舗装切断深さ(m)		合計
アスファルト,Co舗装版厚	t≤15cm	0.023	×	3.75 m	×	0.10	= 0.01 m3	
		0.023	×	m	×		= 0.00 m3	

0.01 m3